



NOTES

1. ALL DROP COMPONENTS (BENDS, TEES, VERTICAL DUCTILE IRON PIPE, PRECAST HORSESHOES, MORTAR, CONNECTIONS TO EXISTING STRUCTURES, AND IF APPLICABLE, REMOVAL OF THE EXISTING DROP SECTION) ARE CONSIDERED INCIDENTAL TO THE "OUTSIDE DROP" BID ITEM.
2. "CRE-SEAL", "RES-SEAL" OR APPROVED EQUIVALENT PRE-CAST GASKETED CONNECTION WILL BE USED FOR CONNECTING PIPE TO MANHOLE FOR PRECAST SECTIONS (SEE DETAIL SS-4).
3. ALL CONNECTIONS TO EXISTING STRUCTURES WILL BE CORE DRILLED.
4. ECCENTRIC CONE WILL BE OFFSET TO THE OUTLET (LOWEST) INVERT SIDE.
5. REFER TO DIVISION 2, PART B, SECTION 2621.3.D.1 FOR ADDITIONAL CONSTRUCTION REQUIREMENTS.
6. REFER TO DIVISION 2, PART A, SECTION 2503.4.C FOR METHOD OF MEASUREMENT.



CITY OF BURNSVILLE - ENGINEERING DEPT.
**SANITARY SEWER
 OUTSIDE DROP SECTION**

Plate No.	SS-5
Revision Date	11/2013
File Location: S:\Details\english\Sanitary Sewer\SS05-Outside Drop MH.dwg	